

<b>ITEM NO.</b>	<b>DESCRIPTION</b>	<b>UNIT OF MEASURE</b>	<b>APPROX. QTY.</b>
201	CLEARING AND GRUBBING, AS PER PLAN	LUMP	1
202	REMOVED, AS PER PLAN	LUMP	1
304	AGGREGATE BASE, AS PER PLAN	C.Y.	500
408	PRIME COAT 0.4 GAL./S.Y.	GAL.	1225
448	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22	C.Y.	380
448	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 2, PG 64-22	C.Y.	305
603	6" PVC SDR-35, TYPE B	FT.	50
603	8" PVC SDR-35, TYPE B	FT.	50
603	12" CPSLP, TYPE B	FT.	50
608	COMBINATION CURB AND SIDEWALK, AS PER PLAN	S.F.	910
609	TYPE 6 BARRIER CURB, AS PER PLAN	FT.	110
614	MAINTAINING TRAFFIC, AS PER PLAN	LUMP	1
638	8" D.I.P. CL 53 WATER MAIN, AS PER PLAN	FT.	3679
638	8" GATE VALVE	EACH	13
638	6" FIRE HYDRANT ASSEMBLY, AS PER PLAN	EACH	9
638	3/4" COPPER SERVICE BRANCHES INCLUDING METER PITS, AS PER PLAN	FT.	5581
659	SEEDING AND MULCHING, AS PER PLAN	S.Y.	2000